
# AAM DURHAM RESIDENCES, LLC 32 & 34 MADBURY ROAD

DURHAM NEW HAMPSHIRE
JULY 2022



#### OWNER:

AAM DURHAM RESIDENCES, LLC 78 BLANCHARD ROAD SUITE 100 BURLINGTON, MA

#### **ENGINEER**



5 RAILROAD STREET NEWMARKET, NH 03857 (603)659-4979


#### SHEET INDEX:


EXISTING CONDITIONS SURVEY
SITE PLAN
GRADING & EROSION CONTROL PLAN
UTILITIES PLAN
LANDSCAPE PLAN
LIGHTING PLAN
CONSTRUCTION DETAILS
FLOOR PLANS
BUILDING ELEVATION & RENDERING PLANS


DATE OF PRINT

JULY 14 2022

HORIZONS ENGINEERING







#### **GENERAL NOTES:**

SUBJECT PROPERTY
32 MADBURY ROAD
TAX MAP 2, LOT 10-3
48 492 ft2± (1.11 Ac±)

OWNER OF RECORD

AAM DURHAM RESIDENCES LLC
78 BLANCHARD ROAD, SUITE 100
BURLINGTON, MA 01803
R.C.R.D. BOOK 4850, PAGE 20

- 1. THE PURPOSE OF THIS PLAN IS TO SHOW THE PROPOSED IMPROVEMENTS AND IMPACTS TO THE PROJECT SITE
- IMPROVEMENTS AND IMPACTS TO THE PROJECT SITE.

  2. THE SUBJECT LOT IS NOT WITHIN A 100-YEAR FLOODPLAIN AS SHOWN ON THE FEMA FIRM#33017C0318E, REVISED 30 SEPTEMBER, 2015
- 3. FIELD SURVEY WAS CONDUCTED BY DOUCET SURVEY IN JUNE
- 4. REMOVE SNOW TO AN OFF-SITE LOCATION WHEN DESIGNATED SNOW AREAS ARE FULL. DO NOT BLOCK SIGHT LINES WITH SNOW.
- 5. VERTICAL DATUM IS BASED ON APPROXIMATE NAVD88 (GEOID12A)
  (±0.2') DERIVED FROM REDUNDANT GPS OBSERVATIONS UTILIZING
  THE KEYNETGPS VRS NETWORK
- 6. THE SOILS ON THE SITE ARE HOLLIS-CHARLTON FINE SAND LOAM, 3 TO 8%.

#### TEST PIT DATA

TEST PITS WERE DUG BY COULSTRING CONSTRUCTION AND LOGGED BY MICHAEL J. SIEVERT OF HORIZONS ENGINEERING ON 19 AUGUST 2021

TEST PIT #1

" TOPSOIL

6-24" FINE SANDY LOAM, GRANULAR LOOSE 24-66" GRAVELY FINE SANDY LOAM, LOOSE

REFUSAL @ 66"

TEST PIT #2 0-18" REFUSAL @ 18"

0-16" REFUSAL @ 16"

TEST PIT #4 0-20" REFUSAL @ 20"

T PIT #5

VERY FINE SANDY LOAM

" VERY FINE SAIDT LOAI
" VERY FINE SILT CLAY
ROOTS TO 39"

PIT #6 ROCK @ 54"

ROOTS TO 24"

ROOTS TO 30"

VERY FINE SANDY LOAM

TEST PIT #7 0-50" REFUSAL @ 50"

> horizons Engineering

Civil and Structural Engineering
Land Surveying and Environmental Consulting

MAINE • NEW HAMPSHIRE • VERMONT

www.horizonsengineering.com

AAM DURHAM RESIDENCES

32 & 34 MADBURY ROAD

DURHAM, NEW HAMPSHIRE

GRADING AND EROSION CONTROL PLAN

NO.	DATE	REVISION DESC	ENG	DWG	
00	2021-12-21	INITIAL SUBMISSION	MCS	MCS	
01	2022-04-05	REVISED PER PLANN	MCS	MCS	
02	2022-05-10	REVISED PER NOD D	MCS	MCS	
03	2022-07-14	REVISED PER DURHA	MCS	MCS	
			DATE:	PROJE	CT #:
	9 3 3 8 8 8 W	Nagase.	2021-12-21	215	85

ENG'D BY: DRAWN BY

CHECK'D BY: ARCHIVE #


C102

MJS

MJS



© 2021 **horizons** *Engliseting* All rights reserved



SEWER STRUCTURE TABLE					
STRUCTURE ID	DETAILS:	PIPES IN:	PIPE OUT		
SMH #1372 (EXISTING)	RIM: 84.07 INV IN: 70.30 INV IN: 70.30 INV OUT: 70.20	(EX) 8" PVC (NEW) 8" PVC	(EX) 8" PVC		
SMH #1512	RIM: 80.26 INV IN: 76.70 INV IN: 76.90 INV IN: 76.70 INV OUT: 75.00	(EX) 5" PVC (EX) 6" PVC (EX) 5" PVC	(NEW) 8" PVC		

DRAIN STRUCTURE TABLE					
STRUCTURE ID	DETAILS:	PIPES IN:	PIPE OUT		
CB #1	RIM: 74.00 INV OUT: 69.50		Pipe - (53), 12" CPP		
CB #2 (DEEP SUMP)	RIM: 78.82 INV OUT: 74.50		Pipe - (51), 12" CPP		
CB #1586	RIM: 70.20 INV IN: 68.00 INV IN: 68.00 INV OUT: 67.90	Pipe - (53), 12" CPP Pipe - (54), 8" CPP	Pipe - (55), 12" RCP		
OCS #1	RIM: 73.10 INV OUT: 69.00		Pipe - (54), 8" CPP		
YD-100	RIM: 76.00 INV OUT: 73.83		Pipe - (52), 6" PVC		

UTILITIES PLAN

© 2021 **horizons** *Inglifering* All rights reserved

FINAL APPROVAL BY DURHAM PLANNING BOARD.

CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER

**GENERAL NOTES:** 

SUBJECT PROPERTY

32 MADBURY ROAD TAX MAP 2, LOT 10-3

48 492 ft2± (1.11 Ac±)

SEPTEMBER, 2015

THE KEYNETGPS VRS NETWORK

PRIOR TO ANY EXCAVATION.

OWNER OF RECORD

BURLINGTON, MA 01803

1. THE PURPOSE OF THIS PLAN IS TO SHOW THE PROPOSED

IMPROVEMENTS AND IMPACTS TO THE PROJECT SITE.

2. THE SUBJECT LOT IS NOT WITHIN A 100-YEAR FLOODPLAIN AS

3. FIELD SURVEY WAS CONDUCTED BY DOUCET SURVEY IN JUNE

4. REMOVE SNOW TO AN OFF-SITE LOCATION WHEN DESIGNATED

SNOW AREAS ARE FULL. DO NOT BLOCK SIGHT LINES WITH SNOW. 5. VERTICAL DATUM IS BASED ON APPROXIMATE NAVD88 (GEOID12A)

(±0.2') DERIVED FROM REDUNDANT GPS OBSERVATIONS UTILIZING

6. THE SOILS ON THE SITE ARE HOLLIS-CHARLTON FINE SAND LOAM, 3

7. CALL 811 DIG-SAFE TO MARK UNDERGROUND UTILITY LOCATIONS

SHOWN ON THE FEMA FIRM#33017C0318E, REVISED 30

AAM DURHAM RESIDENCES LLC

78 BLANCHARD ROAD, SUITE 100

R.C.R.D. BOOK 4850, PAGE 20

DURHAM, NEW HAMPSHIRE

horizons Engineering

**Civil and Structural Engineering** 

Land Surveying and Environmental Consulting

MAINE • NEW HAMPSHIRE • VERMONT

www.horizonsengineering.com

AAM DURHAM RESIDENCES

32 & 34 MADBURY ROAD

IO.	DATE	REVISION DESCRIPTION	ENG	DWG
00	2021-12-21	INITIAL SUBMISSION		MCS
01	2022-04-05	REVISED PER PLANNER COMMENTS	MCS	MCS
02	2022-05-10	REVISED PER NOD DATED 2022-04-22	MCS	MCS
03	2022-07-14	REVISED PER DURHAM COA	MCS	MCS
DATE:			PROJE	CT #:



2021-12-21 21585 ENG'D BY: DRAWN BY MJS CHECK'D BY: ARCHIVE # MJS C103

#### TM 2, LOT 10-4 TM 2, LOT 10-1 HOUSING INITIATIVES OF NEW ENGLAND WENTWORTH DOUGLASS HOSPITAL C/O STEWART PROPERTY MGMT PO BOX 9127 PO BOX 10540 CHARLESTOWN MA 02129 BEDFORD NH 03110-0540 SCRD BOOK 1730, PAGE 20 SCRD BOOK 1783, PAGE 539 - DO NOT PLACE STOCKPILES MATERIALS AGAINST TREES - REMOVE LOAM AND CONST. GRAVEL PAD FOR LAY DOWN AREA INSTALL GAS LINE IN ₱HASE 1, ENSURE PROPER COVER WILL BE MAINTAINED AFTER PHASE 2 \* CÔNSTRŮCTĨÔN ÊXÎT DO NOT ACCESS THE SITE WITH MOUNTABLE BERM X FROM, OR EXIT TO, THE - INSTALL NEW SEWER PIPE NORTH BY MADBURY ROAD TAKE CARE TO AVOID CONFLICT WITH CATCH BASIN TO BE INSTALLED IN PHASE 2 - STUB AND CAP IN PHASE 1. CATCH BASIN LOCATION CONNECT TO BUILDING IN INSTALLED IN PHASE 2 PHASE 2 -INSTALL REPLACÈMENT MANHOLE. TM 2, LOT 10-2 MAG NAIL SET, UP 6" ROBERT HENRY IN POLE #NETCO 13/6/1 SEWER PIPE TO BE ABANDONED -41 GARRISON AVE DURHAM NH 03824 ELEV.=74.74' AFTER NEW MANHOLE CONNECTED SCRD BOOK 1375, PAGE 509 - INSTALL NEW CATCH BASIN - CONNECT EX. LATERALS TO **NEW MANHOLE** REMOVE EXISTING CATCH BASIN LOCATE EXISTING DRAINS NEAR FOUNDATION OF EX. BUILDING, REROUTE FLOW TO DRAIN TO CB 1586 BY SURFACE REMOVE EX. PIPE REMOVE EX. PIPE --- #203A/PSNH/82 AND SAVE FOR REUSE VP #NETT/20/12 - INSTALL NŒW CATCH BASIN NSTALL ORANGE CONSTRUCTION FENCING, MAINTAIN UNTIL ALL GARRISON AVE OUTSIDE WORK IS COMPLETED. - #3/82/20/1/NETT W/"DRUG FREE SCHOOL ZONE" SIGN STUB NEW WATER SERVICE CONNECT TO BUILDING IN PHASE 1 REMOVE EX. CATCH BASIN TOWN APPROVAL. TM 2, LOT 11-1 TORRINGTON MALDEN ONE LLC UEP LIVING LLC 60 K ST SUITE 302 TRUCKS LEAVING THE SITE BOSTON MA 02127 MUST TURN RIGHT ON NEW HAMPSHIRE BETA HOUSING LLC SCRD BOOK 4720, PAGE 149 **GARRISON AVE** C/O SAE FINANCIAL HOLDING CORP 1856 SHERIDAN ROAD EVANSTON IL 60201 SCRD BOOK 3795, PAGE 166 FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER SCALE: 1" = 20'

#### CONSTRUCTION NOTES

- <u>INSPECTION</u> ALL INSPECTION/ OBSERVATION SERVICES FOR THE INSTALLATION OF WATER, WASTEWATER, STORMWATER MANAGEMENT, AND OTHER INFRASTRUCTURE SHALL BE PERFORMED BY AUTHORIZED REPRESENTATIVES OF THE TOWN OF DURHAM AS STIPULATED BY THE DURHAM DEPARTMENT OF PUBLIC WORKS.THE DEVELOPER SHALL REIMBURSE THE TOWN FOR ALL ASSOCIATED INSPECTION/ OBSERVATION
- 2. FIRE ACCESS ACCESS INTO THE SITE FOR FIRE APPARATUS SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION PROCESS. PLEASE CONTACT THE DURHAM FIRE DEPARTMENT AT (603) 868-5531 WITH ANY QUESTIONS ABOUT ACCESS REQUIREMENTS.
- CONSTRUCTION HOURS ALL OUTSIDE CONSTRUCTION ACTIVITY RELATED TO THE DEVELOPMENT OF THIS SITE IS RESTRICTED TO THE HOURS OF 7:00AM TO 6:00PM MONDAY THROUGH FRIDAY AND 9:00AM TO 6:00PM SATURDAY.
- ADDITIONAL INFORMATION FOR ADDITIONAL INFORMATION ABOUT THIS SITE PLAN, OR TO SEE THE COMPLETE PLAN SET, CONTACT THE TOWN OF DURHAM PLANNING DEPARTMENT, 8 NEWMARKET ROAD, DURHAM NH 03824. (603) 868-8064.
- **EROSION AND SEDIMENTATION ALL EROSION AND SEDIMENTATION** CONTROL STRUCTURES SHALL REMAIN IN PLACE AND BE MAINTAINED UNTIL VEGETATION IS ESTABLISHED AND THE GROUND SURFACE IS STABILIZED. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE MONITORED BY THE APPLICANT ON A PERIODIC BASIS DURING CONSTRUCTION AND ANY DEFICIENCIES SHALL BE CORRECTED AS SOON
- <u>BLASTING</u> BLASTING AND ON-SITE CHIPPING (OF STONE) IS RESTRICTED TO THE HOURS OF 9:00AM TO 5:00PM MONDAY THROUGH FRIDAY. IF ANY BLASTING IS NEEDED THE APPLICANT OR CONTRACTOR SHALL OBTAIN A PERMIT FROM THE DURHAM FIRE DEPARTMENT.
- WEEKLY MEETINGS THE APPLICANT/CONTRACTOR SHALL HOLD WEEKLY MEETINGS OR AS SPECIFIED BY THE TOWN ENGINEER WITH APPROPRIATE TOWN DEPARTMENTS TO DISCUSS THE CONSTRUCTION PROCESS AND THE SCHEDULE FOR THE UPCOMING WEEK.
- ROADS AND SIDEWALKS THE APPLICANT/CONTRACTOR SHALL NOT OBSTRUCT ANY ROAD OR SIDEWALK WITHOUT APPROVAL OF THE DURHAM POLICE DEPARTMENT. THE APPLICANT/CONTRACTOR SHALL CONTACT THE POLICE DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO ANY SUCH ACTIVITY. THE POLICE DEPARTMENT WILL DETERMINE WHETHER OR NOT A POLICE DETAIL IS NEEDED.
- CONSTRUCTION VEHICLE ACCESS TRUCK TRAFFIC APPROACHING FROM THE SOUTH OR EAST SHALL COME BY ROUTE 108, THEN TURN ONTO MAIN STREET AT THE TRAFFIC LIGHT, THEN TURN ONTO MADBURY ROAD TO THE SITE.

TRUCK TRAFFIC APPROACHING FORM THE NORTH OR WEST SHALL COME BY MAIN STREET (FROM ROUTE 4 OR ROUTE 155A), THEN TURN ONTO GARRISON AVENUE, THEN TURN ONTO MADBURY ROAD TO THE SITE.

TRUCK TRAFFIC LEAVING (TO ANY DIRECTION) SHALL TURN SOUTH ON

MADBURY ROAD, THEN RIGHT ONTO GARRISON AVENUE, THEN RIGHT ONTO MAIN STREET (TO ROUTE 4 OR ROUTE 155A).

- 10. PEDESTRIAN ACCESS THE CONTRACTOR SHALL PROVIDE A MINIMUM 5 FOOT WIDE PEDESTRIAN ACCESS FOR ALL INGRESS AND EGRESS LOCATIONS FOR THE EXISTING BUILDING.
- 11. NO PARKING ON GARRISON AVE. DURING CONSTRUCTION. ARRANGEMENTS FOR OFF SITE PARKING IS THE RESPONSIBILITY OF THE CONTRACTOR.

#### CONSTRUCTION SEQUENCE

- 1. COMPLETE PRECONSTRUCTION MEETING AS REQUIRED BY
- 2. INSTALL ALL EROSION CONTROLS AND CONSTRUCTION EXIT
- BEFORE EARTHWORKS START.
- 3. INSTALL PROPOSED SANITARY SEWER. 4. INSTALL PROPOSED CATCH BASINS, EXCEPT FOR THE CATCH
- BASIN THAT WILL BE PART OF THE NEW PARKING LOT.
- 5. CLEAR TREES WITHIN THE GRADING LIMITS. 6. MONITOR AND MAINTAIN EROSION CONTROLS AS NEEDED.
- 7. GRUB WITHIN GRADING LIMITS..

## horizons Engineering

#### **Civil and Structural Engineering** Land Surveying and Environmental Consulting

MAINE • NEW HAMPSHIRE • VERMONT www.horizonsengineering.com

#### AAM DURHAM RESIDENCES 32 & 34 MADBURY ROAD

DURHAM, NEW HAMPSHIRE

#### PHASE I CONSTRUCTION PLAN


VO.	DATE	REVISION DESC	ENG	DWG	
00	2022-04-06	INITIAL SUBMISSION	MCS	MCS	
01	2022-05-10	REVISED PER NOD D	MCS	MCS	
02	2022-05-27	REVISED PER DPW C	MCS	MCS	
03	2022-07-14	REVISED PER DURHA	MCS	MCS	
			DATE:	PROJE	CT #:
	OF HEN	V HAPPA	2022-04-06	215	85



CHECK'D BY: ARCHIVE # MJS

C104

ENG'D BY: DRAWN BY



#### CONSTRUCTION NOTES

- <u>INSPECTION</u> ALL INSPECTION/ OBSERVATION SERVICES FOR THE INSTALLATION OF WATER, WASTEWATER, STORMWATER MANAGEMENT, AND OTHER INFRASTRUCTURE SHALL BE PERFORMED BY AUTHORIZED REPRESENTATIVES OF THE TOWN OF DURHAM AS STIPULATED BY THE DURHAM DEPARTMENT OF PUBLIC WORKS.THE DEVELOPER SHALL REIMBURSE THE TOWN FOR ALL ASSOCIATED INSPECTION/ OBSERVATION
- 2. FIRE ACCESS ACCESS INTO THE SITE FOR FIRE APPARATUS SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION PROCESS. PLEASE CONTACT THE DURHAM FIRE DEPARTMENT AT (603) 868-5531 WITH ANY QUESTIONS ABOUT ACCESS REQUIREMENTS.
- CONSTRUCTION HOURS ALL OUTSIDE CONSTRUCTION ACTIVITY RELATED TO THE DEVELOPMENT OF THIS SITE IS RESTRICTED TO THE HOURS OF 7:00AM TO 6:00PM MONDAY THROUGH FRIDAY AND 9:00AM TO 6:00PM SATURDAY.
- ADDITIONAL INFORMATION FOR ADDITIONAL INFORMATION ABOUT THIS SITE PLAN, OR TO SEE THE COMPLETE PLAN SET, CONTACT THE TOWN OF DURHAM PLANNING DEPARTMENT, 8 NEWMARKET ROAD, DURHAM NH 03824. (603) 868-8064.
- **EROSION AND SEDIMENTATION ALL EROSION AND SEDIMENTATION** CONTROL STRUCTURES SHALL REMAIN IN PLACE AND BE MAINTAINED UNTIL VEGETATION IS ESTABLISHED AND THE GROUND SURFACE IS STABILIZED. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE MONITORED BY THE APPLICANT ON A PERIODIC BASIS DURING CONSTRUCTION AND ANY DEFICIENCIES SHALL BE CORRECTED AS SOON
- BLASTING BLASTING AND ON-SITE CHIPPING (OF STONE) IS RESTRICTED TO THE HOURS OF 9:00AM TO 5:00PM MONDAY THROUGH FRIDAY. IF ANY BLASTING IS NEEDED THE APPLICANT OR CONTRACTOR SHALL OBTAIN A PERMIT FROM THE DURHAM FIRE DEPARTMENT.
- WEEKLY MEETINGS THE APPLICANT/CONTRACTOR SHALL HOLD WEEKLY MEETINGS OR AS SPECIFIED BY THE TOWN ENGINEER WITH APPROPRIATE TOWN DEPARTMENTS TO DISCUSS THE CONSTRUCTION PROCESS AND THE SCHEDULE FOR THE UPCOMING WEEK.
- ROADS AND SIDEWALKS THE APPLICANT/CONTRACTOR SHALL NOT OBSTRUCT ANY ROAD OR SIDEWALK WITHOUT APPROVAL OF THE DURHAM POLICE DEPARTMENT. THE APPLICANT/CONTRACTOR SHALL CONTACT THE POLICE DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO ANY SUCH ACTIVITY. THE POLICE DEPARTMENT WILL DETERMINE WHETHER OR NOT A POLICE DETAIL IS NEEDED.
- CONSTRUCTION VEHICLE ACCESS TRUCK TRAFFIC APPROACHING FROM THE SOUTH OR EAST SHALL COME BY ROUTE 108, THEN TURN ONTO MAIN STREET AT THE TRAFFIC LIGHT, THEN TURN ONTO MADBURY ROAD TO THE SITE.

TRUCK TRAFFIC APPROACHING FORM THE NORTH OR WEST SHALL COME BY MAIN STREET (FROM ROUTE 4 OR ROUTE 155A), THEN TURN ONTO GARRISON AVENUE, THEN TURN ONTO MADBURY ROAD TO THE SITE.

MADBURY ROAD, THEN RIGHT ONTO GARRISON AVENUE, THEN RIGHT ONTO MAIN STREET (TO ROUTE 4 OR ROUTE 155A). 10. PEDESTRIAN ACCESS - THE CONTRACTOR SHALL PROVIDE A MINIMUM 5

TRUCK TRAFFIC LEAVING (TO ANY DIRECTION) SHALL TURN SOUTH ON

FOOT WIDE PEDESTRIAN ACCESS FOR ALL INGRESS AND EGRESS LOCATIONS FOR THE EXISTING BUILDING.

11. NO PARKING ON GARRISON AVE. DURING CONSTRUCTION. ARRANGEMENTS FOR OFF SITE PARKING IS THE RESPONSIBILITY OF THE CONTRACTOR.

#### CONSTRUCTION SEQUENCE

- 1. INSTALL ALL EROSION CONTROLS AND CONSTRUCTION EXIT BEFORE EARTHWORKS START.
- 2. INSTALL STORMWATER POND INSTALL PROPOSED CATCH BASINS, EXCEPT FOR THE CATCH BASIN THAT WILL BE PART OF THE NEW PARKING LOT.
- 3. REMOVE EXISTING PARKING LOT AS NEEDED.
- 4. BEGIN CONSTRUCTION OF NEW BUILDING FOUNDATION. 5. BEGIN CONSTRUCTION OF NEW PARKING LOT AND
- ESTABLISH FINAL GRADES OF THE SITE.
- 6. DEPENDING ON THE TIME OF COMPLETION OF THE PARKING LOT, FINAL PAVING MAY BE DELAYED TO FOLLOWING
- 7. MONITOR AND MAINTAIN EROSION CONTROLS AS NEEDED.

### horizons ingineering

**Civil and Structural Engineering** Land Surveying and Environmental Consulting

> MAINE • NEW HAMPSHIRE • VERMONT www.horizonsengineering.com

AAM DURHAM RESIDENCES 32 & 34 MADBURY ROAD

DURHAM, NEW HAMPSHIRE

#### PHASE II CONSTRUCTION PLAN

VO.	DATE	REVISION DESC	ENG	DWG	
00	2022-04-05	INITIAL SUBMISSION	MCS	MCS	
01	2022-05-10	REVISED PER NOD DATED 2022-04-22		MCS	MCS
02	2022-05-27	REVISED PER DPW C	MCS	MCS	
03	2022-07-14	REVISED PER DURHA	MCS	MCS	
			DATE:	PROJE	CT #:
	OF HEN	HALL	2021-12-21	215	85

ENG'D BY: DRAWN BY


CHECK'D BY: ARCHIVE #

C105

MJS



© 2021 **horizons** Ingineering All rights reserve



SC	ALE: 1" = 20'	
Do not heavily prune the tree at planting. Prune only cross-over limbs, co-dominant leaders, and broken or dead branches. Some interior twigs and lateral branches may be pruned; however, Do NOT remove the terminal buds of branches that extend to the edge of the crown.  Trees less than 3" in caliper shall be staked		Trees greater than 3" in caliper shall be guyed with three guys per tree, spaced evenly around the trunk with 12 gauge wire. Plastic hose sections shall be used at attachment to trees. Each guy wire shall be flagged with a visual marker. 24" stakes or metal drive anchors shall be used to anchor the guy wires. Stakes/Anchors shall be driven 12" min. outside the edge of the planting pit into stable soil. Remove all guying NO LATER than the end of the first growing season after planting.
with three stakes per tree, spaced evenly around the trunk with 12 gauge wire. Plastic hose sections shall be used at attachment to trees. Each wire shall be flagged with a visual marker. 5' long min. wooden stakes shall be used to anchor the wires. Stakes shall be		6" Corrugated PVC tree sock
driven at least 12" outside the edge of the planting pit into stable soil. Remove all staking NO LATER than the end of the first growing season after planting.		Each tree must be planted such that the original trunk flare is visible at the top of the root ball. Trees where the original trunk flare is not visible may be rejected. Do NOT cover the top of the root ball with soil.  Before planting Contractor shall inspect the rootball for the
Mark the north side of the tree in the nursery. Rotate the tree to face north at the site whenever possible.	1'-0" Mulch Ring	location of the original root flare. If the original root flare is not visible at the top of the root ball then the Contractor shall then gently remove from the top of the root ball any excess soil from nursery operations that may be covering the original root flare. All secondary and girdling roots
4 in. high earth saucer beyond edge of root ball	5'-0" diameter, min. (8FT.) diam. preferred	shall be removed prior to planting. Trees with 4" or more of extraneous soil and/or adventitious roots greater than 1/8" shall be rejected. The tree shall be planted with the original root flare at or slightly (2-3") above surrounding finished grade.
2 IN. max. Mulch. Do NOT place mulch in contact with tree trunk. Maintain the mulch weed-free for a minimum of three years after planting.		
Tamp soil around root ball base firmly with foot pressure so that root ball does not shift.		Backfill with existing soil, in sandy and heavy clay soils add 20% max. by volume composted organic material to the existing soil.  Remove all twine, rope, wire, and burlap
Place root ball on unexcavated or tamped	2 times the diameter of the root ball	If plant is shipped with a wire basket around the root ball, prior to planting, the contractor shall cut away the bottom

- Permeable area in which tree is

to be planted shall be no less than

a 3' wide radius from the base of

of the wire basket, leaving the sides in place. Once the

tree is placed and faced, the contractor shall remove the


remainder of the wire basket and backfill the planting pit as

Tree Planting Detail

Plant L	ist				
TREES					
Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Mal	Malus 'Prairiefire'	Prairiefire Crabapple	1	2-2.5" cal	BB
Ua	Ulmus americana 'Princeton'	Princeton American Elm	2	3-3.5" cal.	BB
Cc	Crataegus crus-galli 'Inermis'	Thornless Cockspur Hawthorn	3	2-2.5" cal	BB
Z	Zelkova serrata 'Green Vase'	Green Vase Zelkova	1	2-2.5" cal	
SHRUBS					
Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Hy	Hydrangea paniculata 'Litlle Lime'	Little Lime Hydrangea	18	5 gal	
lg	llex glabra 'Shamrock'	Shamrock Inkberry	27	5 gal	Full & full to the ground Bi
Rhus	Rhus aromatica 'Grow-Low'	Grow Low Sumac	22	18-24"	BB
Ros	Rosa 'Apricot Drift'	Apricot Drift Rose	20	3 gal	
Ros2	Rosa 'Sunny Knockout'	Sunny Knockout Rose	12	5 gal	
Tax	Taxus media 'Everlow'	Everlow Yew	50	3 gal	
PERENNIA	ALS, GROUNDCOVERS, VINES and ANNUA	ALS			
Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Cal	Calamagrostis acutifolia 'Karl Foerster'	Feather Reed Grass	40	1 gal	

#### Landscape Notes

- Design is based on drawings by Horizons Engineering dated 5/10/2022 and may require adjustment due to actual field conditions.
- The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site
- Erosion Control shall be in place prior to construction.
- Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water bodies, Wetlands and/or drainage ways prior to any construction.
- The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies or changes in layout and/or grade relationships prior to construction.
- 6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request.
- Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor
- 10. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 1-888-344-7233.
- 11. The Contractor shall procure any required permits prior to construction.
- 12. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
- 13. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a contractor is aware of a potential issue, and does not bring it to the attention of the landscape architect or owner's representative immediately, they may be responsible for the labor and materials associated with
- 14. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- 15. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity
- discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- 16. All plants shall be legibly tagged with proper botanical name. The Contractor shall guarantee all plants for not less than one year from time of acceptance.
- 18. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- 19. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- 20. Hose bibs shall be located adjacent to the front and rear entry, in order to provide water to plant material.
- 21. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering of plants. Plants shall be appropriately watered prior to, during and after planting. It is the contractor's responsibility to provide clean water suitable for plant health from off site, should it not be available on site.
- 22. All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- 23. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and ½" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length.
- Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be black. 24. Drip strip shall extend to 6" beyond roof overhang and shall be edged with 3/16" thick metal edger.
- 25. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- 26. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy. Within the sight distance triangles at vehicle intersections the canopies shall be raised to 8' min.
- 27. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- Landscape Architect is not responsible for the means and methods of the contractor.
- 29. Low phosphorus/slow release nitrogen fertilizers for landscaping materials shall be used.





DRAFT NOT FOR CONSTRUCTION

> © 2021 horizons



**Land Surveying and Environmental Consulting** MAINE · NEW HAMPSHIRE · VERMONT

www.horizonsengineering.com

AAM DURHAM RESIDENCES

32 & 34 MADBURY ROAD


DURHAM, NEW HAMPSHIRE


#### LANDSCAPE PLAN


022-03-01	INITIAL SUBMISSION			01
022-04-06	PER TOWN COMMEN	VM	01	
)22-05-16	PER TOWN COMMEN	VM	01	
		DATE:	PROJE	CT #:
		2022-03-01	215	85
		ENG'D BY:	DRAW	N BY:
		VM	17	М
		CHECK'D BY:	ARCHI	VE #:
		RW	H	_

LA101

All rights reserved







UNDISTURBED GROUND -

- 36" MIN. FENCE POSTS, DRIVEN MIN. 16" INTO GROUND

EMBED FILTER CLOTH -

MIN. 8" INTO GROUND


#### -BUILT IN OVERFLOW PORTS (2) FOR HIGH DRAINAGE WATER FLOW STRUCTURE — NON-WOVEN GEOTEXTILE **CATCH BASIN PROTECTION INSERT TYPE**


NO SCALE

WATER SERVICE CONNECTION

NOT TO SCALE

© 2021 **horizons** *Inducering* All rights reserved





CONSTRUCTION NOTES FOR SEDIMENT FENCE

WOVEN WIRE FENCE, IF REQUIRED,

2. FILTER CLOTH TO BE FASTENED

FOLDED AND STAPLED.

RECOMMENDATIONS.

TO BE FASTENED SECURELY TO FENCE

POSTS WITH WIRE TIES OR STAPLES.

SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT

TOP, MID SECTION, AND BOTTOM.

5. 12" DIAMETER FILTREXX SILTSOXX

3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN

4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND

SEDIMENT FENCE, OR 50% OF CAPACITY IS USED.

FENCE IF INSTALLED PER MANUFACTURER'S

MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE

SHALL BE CONSIDERED AN ACCEPTABLE EQUAL TO SEDIMENT

EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES,

WOVEN WIRE FENCE -


WITH FILTER CLOTH OVER

<u>+ FLOW+ +</u>

(14-1/2 GA. MIN., MAX. 6" MESH SPACING)

#### MODULAR RETAINING WALL DETAIL

NO SCALE



horizons ingineering

**Civil and Structural Engineering** 

Land Surveying and Environmental Consulting


MAINE • NEW HAMPSHIRE • VERMONT


www.horizonsengineering.com

AAM DURHAM RESIDENCES

32 & 34 MADBURY ROAD

DURHAM, NEW HAMPSHIRE







Max: 829cd

Schedule

Т

C



# MADBURY Site

#### Designer

Heidi G. Connors Visible Light, Inc. 24 Stickeny Terrace Suite 6 Hampton, NH 03842 Date

4/6/2022

Scale 1"=20'

**Drawing No.** 

Summary

2 of 2