


REFERENCE PLAN:

"SUBDIVISION PLAN - OYSTER RIVER DEVELOPMENT - SECTION 2 LOTS 8 THROUGH 24" - SCALE 1"=50', DATED FEBRUARY 21, 1959 - PREPARED BY G.L. DAVIS AND ASSOCIATES AND RECORDED IN THE SCRD AS PLAN 30A POCKET 4 FOLDER 3

NOTES

- THE OWNERS OF RECORD FOR TAX MAP 214 LOT 11 ARE ARTHUR L. MCMANUS, JR. & DEBORAH MCMANUS OF 29 FRONTIER STREET, RYE, NH 03870. SEE S.C.R.D. BK. 5180 PG. 597 DATED 4/29/2024.
- THE PURPOSE OF THIS PLAN IS DEPICT THE PROPOSED HOUSE ADDITION AND DRIVEWAY IMPROVEMENTS AND EXISTING OBSERVABLE CONDITIONS FOR TAX MAP 214 LOT 11, AS SHOWN.
- 3. ZONING FOR TAX MAP 214 LOT 11 IS RC (RESIDENCE COASTAL). MINIMUM BUILDING SETBACKS INCLUDE 125 FT. TOWN SHORELAND, 50 FT. SIDE, AND 30 FT. FRONT.
- 4. THE SURFACE FEATURES SHOWN WERE DEVELOPED FROM THE REFERENCE PLAN CITED HEREON TOGETHER WITH AN ON THE GROUND FIELD SURVEY BY THIS OFFICE DURING THE MONTH OF AUGUST, 2024.
- 5. HORIZONTAL ORIENTATION IS BASED UPON THE REFERENCE PLAN NOTED HEREON. VERTICAL DATUM IS NAVD88 PER A GPS CORS SOLUTION.
- 6. TAX MAP 214 LOT 11 IS SUBJECT TO NH SHORELAND WATER QUALITY PROTECTION ACT (RSA 483-B) AND ITS ASSOCIATED RULES, ENV-WQ 1400.
- 7. LOT LINES ARE SHOWN PER THE REFERENCE PLAN NOTED HEREON. THIS IS NOT TO BE CONSIDERED A BOUNDARY SURVEY BY THIS OFFICE.
- 8. A PORTION OF THE PARCEL IS SUBJECT TO THE 100 YEAR FLOOD HAZARD AREA ZONE AE PER FEMA FIRM MAP #33017CO320E, REVISED DATE 9/30/2015.
- 9. NO EASEMENTS WERE RECOVERED BY THIS OFFICE FOR THE SUBJECT PARCEL.



REV. PER CLIENT REVIEW

DESCRIPTION

SITE PLAN

TAX MAP 214 LOT 11

(4 RIVERVIEW COURT)

DURHAM, NEW HAMPSHIRE

PREPARED FOR:

ARTHUR MCMANUS

29 FRONTIER STREET, RYE, NH 03870

ARTHUR L. MCMANUS, JR.

& DEBORAH MCMANUS
29 FRONTIER STREET, RYE, NH 03870

SCALE: 1" = 20'

A 12/17/24

REV. DATE

DECEMBER 11, 2024

- | CLR | CEB

C/O DR

Surveying \oplus Engineering \oplus Land Planning \oplus Permitting \oplus Septic Designs



206 Elm Street, Milford, NH 03055 45 Roxbury Street, Keene, NH 03431 Phone: (603) 672-5456 Fax: (603) 413-5456 www.FieldstoneLandConsultants.com

FILE: 3886SP02C.dwg PROJ. NO. 3886.00 SHEET: SP-1 PAGE NO. 1 OF 3

1. PRIOR TO STARTING ANY WORK ON THE SITE THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES.

2. ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN ACCORDANCE WITH STANDARDS AND SPECIFICATIONS THEREOF IN NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICE STORM WATER MANUALS, VOLUME 1-3, LATEST EDITION.

3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PER PLANS AND DETAILS. PERIMETER CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF EARTH DISTURBING ACTIVITIES.

4. INSTALL INLET PROTECTION AROUND ALL STORM DRAIN STRUCTURES. INLET PROTECTION BMP'S SHALL REMAIN UNTIL THE SITE IS STABILIZED. CONSTRUCTION OF STORMWATER BASINS AND TREATMENT SWALES SHALL OCCUR PRIOR TO AND EARTH MOVING OPERATION THAT WILL INFLUENCE STORM WATER RUNOFF.

5. THE WORK AREA SHALL BE GRADED, SHAPED AND OTHERWISE DRAINED IN SUCH A MANNER AS TO MINIMIZE SOIL EROSION, SILTATION OF DRAINAGE CHANNELS, DAMAGE TO EXISTING VEGETATION, AND DAMAGE TO PROPERTY OUTSIDE THE LIMITS OF THE WORK AREA.

6. EXISTING VEGETATION IS TO REMAIN UNDISTURBED WHEN POSSIBLE.

7. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED AT LEAST ONCE A WEEK AND AFTER EVERY 0.25-INCH OR GREATER RAINFALL. SEDIMENTS SHALL BE DISPOSED OF IN AN UPLAND AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF-SITE AND BE PERMANENTLY STABILIZED.

8. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION. AT NO TIME SHALL THE TOTAL UNSTABILIZED DISTURBED AREA, INCLUDING LOT DISTURBANCES, BE GREATER THAN FIVE (5) ACRES.

9. THE LAND AREA EXPOSED SHALL BE KEPT TO THE SHORTEST PRACTICAL PERIOD OF TIME. ALL NON-ACTIVE DISTURBED AREAS SHALL BE STABILIZED WITHIN 30 DAYS OF THE DISTURBANCE. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF FINAL GRADING.

10. DITCHES, SWALES AND DRAINAGE BASINS SHALL BE CONSTRUCTED DURING THE INITIAL PHASE OF CONSTRUCTION AND STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.

11. AN AREA SHALL BE CONSIDERED STABILIZED IF ONE OF THE FOLLOWING HAS OCCURRED:

A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED; B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;

C. A MINIMUM OF 3-INCHES OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIPRAP, HAS BEEN INSTALLED: OR

D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

12. EROSION CONTROL BLANKETS SHALL BE INSTALLED ON ALL SLOPES THAT ARE STEEPER THAN 3:1 (HORIZONTAL / VERTICAL). UNLESS OTHERWISE SPECIFIED THE CONTRACTOR SHALL USE NORTH AMERICAN GREEN SC150, OR

13. ALL AREAS RECEIVING EROSION CONTROL STONE OR RIPRAP SHALL HAVE A GEOTEXTILE MATERIAL INSTALLED BELOW THE STONE (SEE APPROPRIATE DETAILS).

14. ALL DISTURBED AREAS TO TURF FINISHED SHALL BE COVERED WITH A MINIMUM THICKNESS OF 6 INCHES OF

COMPACTED LOAM. LOAM SHALL BE	COVERED WITH THE APP	ROPRIATE SEED MIXTURE AS IND	ICATED BELOW:	
PERMANENT SEED (LAWN AREAS)	LBS / 1,000 SQ. FT.	PERMANENT SLOPE SEED MIX	LBS / 1,000 SQ. FT.	
CREEPING RED FESCUE PERENNIAL RYEGRASS KENTUCKY BLUEGRASS REDTOP	0.92 LBS 1.15 LBS 0.58 LBS 0.12 LBS	CREEPING RED FESCUE PERENNIAL RYEGRASS REDTOP ALSIKE CLOVER BIRDSFOOT TREFOIL	0.80 LBS 0.69 LBS 0.12 LBS 0.12 LBS	
APPLICATION RATE TOTALS 2.8 LBS PER 1,000 SF		**APPLICATION RATE TOTALS *1.85 LBS PER 1,000 SF**		

15. TEMPORARY STABILIZATION OF DISTURBED AREAS: STRIPPED SOIL SHALL BE STOCKPILED UNCOMPACTED, AND STABILIZED AGAINST EROSION AS OUTLINED BELOW: SEED BED PREPARATION: 10-10-10 FERTILIZATION TO BE SPREAD AT THE RATE OF 7 LBS. PER 100 SF AND AGRICULTURAL LIMESTONE AT A RATE OF 90 LBS PER 1000 SF AND INCORPORATED INTO THE SOIL. THE SOIL, FERTILIZER AND LIMESTONE SHALL BE TILLED TO PREPARE FOR SEEDING.

A. SEED MIXTURE: USE ANY OF THE FOLLOWING:

<u>SPECIES</u>	RATE PER 1,000 SF	<u>DEPTH</u>	SEEDING DATES
WINTER RYE OATS	2.5 LBS 2.5 LBS	1 INCH 1 INCH	8/15 TO 9/15 4/15 TO 10/15
ANNUAL RYEGRASS	1.0 LBS	0.25 INCH	8/15 TO 9/15

B. MULCHING: MULCH SHOULD BE USED ON HIGHLY ERODIBLE AREAS, AND WHERE CONSERVATION OF MOISTURE WILL FACILITATE PLANT ESTABLISHMENT AS FOLLOWS:

 DIN ESTABLISHMENT AS TOLL	0110.	
<u>TYPE</u>	RATE PER 1,000 SF	USE AND COMMENTS
STRAW	70 TO 90 LBS	MAY BE USED WITH PLANTINGS, MUST BE ANCHORED TO BE USED ALONE
WOOD CHIPS OR BARK MULCH	460 TO 920 LBS	USED WITH TREE AND SHRUB PLANTING
FIBROUS MATTING	AS RECOMMENDED BY MANUFACTURER	MUST BE BIODEGRADABLE. USE IN SLOPE AREAS AND AREAS DIFFICULT TO VEGETATE
CRUSHED STONE 1/4" TO 1-1/2" DIA.	SPREAD TO GREATER THAN 1/2" THICKNESS	USE IN SPECIFIC AREAS AS SHOWN ON PLAN OR AS NEEDED

16. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE (CRITICAL TIME FRAMES OR VARIABLE SITES) THEN APPLY FERTILIZER AT A RATE OF 11 POUNDS PER 1,000 SF AND LIMESTONE AT A RATE OF 90 POUNDS PER 1,000 SF. FERTILIZER SHALL BE LOW PHOSPHATE (LESS THAN

17. CAUTION SHOULD BE TAKE WHEN THE PROPERTY IS LOCATED WITHIN 250 FEET OF A WATER BODY. IN THIS CASE ALL FERTILIZERS SHALL BE RESTRICTED TO A LOW PHOSPHATE, SLOW RELEASE NITROGEN FERTILIZER. SLOW RELEASE FERTILIZERS MUST BE AT LEAST 50% SLOW RELEASE NITROGEN COMPONENT. NO FERTILIZER EXCEPT LIMESTONE SHALL BE APPLIED WITHIN 25 FEET OF THE SURFACE WATER. THESE ARE REGULATED LIMITATIONS.

18. PERMANENT OR TEMPORARY COVER MUST BE IN PLACE BEFORE THE GROWING SEASON ENDS (SEE WINTER CONSTRUCTION NOTES). NO DISTURBED AREAS SHALL BE LEFT EXPOSED DURING THE WINTER MONTHS.

19. A VIGOROUS DUST CONTROL PROGRAM SHALL BE APPLIED BY THE SITE CONTRACTOR. DUST SHALL BE MANAGED THROUGH THE USE OF WATER AND/OR CALCIUM CHLORIDE.

20. IN NO WAY ARE THE MEASURES INDICATED ON THE PLANS OR IN THESE NOTES TO BE CONSIDERED ALL INCLUSIVE. THE CONTRACTOR SHALL USE JUDGMENT TO INSTALL ADDITIONAL EROSION CONTROL MEASURES AS SITE CONDITIONS, WEATHER OR CONSTRUCTION METHODS WARRANT.

21. FOLLOWING PERMANENT STABILIZATION, TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND ACCUMULATED SEDIMENTATION IS TO BE DISPOSED OF IN AN APPROVED LOCATION, OUTSIDE OF JURISDICTIONAL

22. LOT DISTURBANCE OTHER THAN SHOWN ON THE APPROVED PLANS, SHALL NOT COMMENCE UNTIL AFTER THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.

23. THE CONTRACTOR AND OWNER ARE RESPONSIBLE FOR OBSERVING AND MANAGING THE PROJECT PER RSA 430:53 AND AGR 3800 REGARDING INVASIVE SPECIES (PLANTS AND INSECTS). NO INVASIVE SPECIES PLANT OR INSECT SHALL BE INTRODUCED ONTO THE SITE.

EROSION CONTROL NOTES

CONTACT DIG SAFE 72 HOURS PRIOR TO CONSTRUCTION DIGSAFE.COM OR DIAL 8 1 1 CALL 811 - KNOW WHAT'S BELOW

1. ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED. STABILIZATION METHODS SHALL INCLUDE SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

2. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.

3. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL OR PROPERLY INSTALLED EROSION CONTROL BLANKETS COVERED WITH HAY. OTHER STABILIZATION OPTIONS ARE TO BE APPROVED BY THE APPROPRIATE AGENCIES AND THE DESIGN ENGINEER. IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER MONTHS THEN THE ROAD SHOULD BE CLEARED OF ACCUMULATED SNOW AFTER EACH STORM EVENT.


WINTER CONSTRUCTION NOTES	2
WINTERCONSTRUCTION NOTES	DT - 1

- 1. INSTALL SILTATION CONTROL FENCES IN LOCATIONS SHOWN HEREON. <u>EROSION AND SEDIMENTATION CONTROL</u> MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH MOVING OPERATION.
- 2. INSTALL STABILIZED CONSTRUCTION EXIT(S).
- 3. CUT AND CLEAR TREES; DISPOSE OF DEBRIS. STUMPS ARE TO BE REMOVED FROM THE SITE AND DISPOSED OF
- 4. REMOVE TOPSOIL AND STOCKPILE AWAY FROM ANY WETLAND. STABILIZE STOCKPILE IMMEDIATELY BY SEEDING. PLACE SILT FENCE AROUND THE DOWN SLOPE SIDE OF EARTH STOCKPILES.
- 5. ROUGH GRADE SITE CONSTRUCT DRAINAGE BASINS AND DRAINAGE SWALES DURING INITIAL PORTION OF CONSTRUCTION. STABILIZE IMMEDIATELY PER THE CONSTRUCTION AND EROSION CONTROL DETAILS. DO NOT DIRECT STORM WATER RUNOFF TO THESE STRUCTURES UNTIL A HEALTHY VEGETATIVE COVER IS ESTABLISHED.
- 6. BEGIN BUILDING CONSTRUCTION.
- 7. CONSTRUCT GRAVEL PARKING AREA (PAVEMENT OPTIONAL) AND BUILDING PAD. INSTALL UTILITIES AND STRUCTURES. ALL CUT AND FILL SLOPES SHALL BE STABILIZED UPON COMPLETION OF ROUGH GRADING PER THE THE EROSION
- 8. INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS AND AFTER EVERY 0.25" OR GREATER
- 9. DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, CULVERTS, DITCHES, SILTATION FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 10. FINISH GRADING TO PREPARE FOR PAVING (IF ANY) AND LOAMING. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL GRADING.
- 11. FINISH PAVING (IF ANY). PERMANENT SEEDING SHALL BE PERFORMED UPON COMPLETION OF PARKING AREA (SEE
- 12. COMPLETE PERMANENT SEEDING AND LANDSCAPING.


EROSION CONTROL NOTES).


- 13. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED.
- 14. ALL STRUCTURES SHALL BE CLEANED OF SEDIMENTS ONCE CONSTRUCTION IS COMPLETE.





VIEW LOOKING UPSTREAM





PROFILE - CHECK DAM SPACING

<u>NOTES:</u>

DT - 1

STONE CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH.

2. THE MAXIMUM CONTRIBUTING DRAINAGE AREA TO THE CHECK DAM SHOULD BE LESS THAN ONE ACRE.


3. STONE CHECK DAMS SHOULD NOT BE USED IN A FLOWING STREAM.

STONE CHECK DAMS SHOULD BE CONSTRUCTED OF WELL-GRADED ANGULAR 2 TO 3 INCH STONE. THE INSTALLATION OF 3/4-INCH STONE ON THE UPGRADIENT FACE IS RECOMMENDED FOR BETTER

WHEN INSTALLING STONE CHECK DAMS THE CONTRACTOR SHALL KEY THE STONE INTO THE CHANNEL BANKS AND EXTEND THE STONE BEYOND THE ABUTMENTS A MINIMUM OF 18-INCHES TO PREVENT FLOW AROUND THE DAM.

6. STONE CHECK DAMS SHOULD BE REMOVED ONCE THE SWALE OR DITCH HAS BEEN STABILIZED UNLESS OTHERWISE SPECIFIED.

STONE CHECK DAM



FLOW

AREAS

DUMP STRAP-

VEGETATED


AREAS


FLOW

- 2. TO INSTALL SACK, REMOVE CATCH BASIN GRATE AND PLACE SACK IN OPENING. HOLD OUT APPROXIMATELY SIX INCHES
- 3. THE SACK SHOULD BE INSPECTED AFTER EVERY STORM, OR ONCE EVERY TWO WEEKS, WHICH EVER OCCURS FIRST.
- 4. THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF THE CORD IS COVERED WITH SEDIMENT, THE SACK SHOULD BE EMPTIED. EMPTY THE SACK AWAY FROM THE CATCH BASIN TO PREVENT SEDIMENT FROM RE-ENTERING THE CATCH BASIN. EMPTY THE SACK PER THE MANUFACTURES RECOMMENDATIONS.

5. REPLACE THE SACK IN THE CATCH BASIN AFTER THE SACK HAS BEEN EMPTIED. ONCE CONSTRUCTION IS COMPLETE AND ALL DISTURBED AREAS HAVE BEEN STABILIZED BY PAVING OR A HEALTHY VEGETATIVE COVER, REMOVE THE SACK FROM THE CATCH BASINS.

SILT SACK SEDIMENT FILTER






- 1. SILT FENCES SHOULD NOT BE USED ACROSS STREAMS, CHANNELS, SWALES, DITCHES OR OTHER
- 2. SILT FENCE SHOULD BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS POSSIBLE AND THE ENDS OF THE SILT FENCE SHOULD BE FLARED UPSLOPE.

DRAINAGE WAYS.

- 3. IF THE SITE CONDITIONS INCLUDE FROZEN GROUND, LEDGE OR THE PRESENCE OF HEAVY ROOTS THE BASE OF THE FABRIC SHOULD BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH
- 4. SILT FENCES PLACED AT THE TOE OF SLOPES SHOULD BE INSTALLED AT LEAST 6 FEET FROM THE TOE TO ALLOW SPACE FOR SHALLOW PONDING AND ACCESS FOR MAINTENANCE.
- 5. THE MAXIMUM SLOPE ABOVE THE FENCE SHOULD BE 2:1 AND THE MAXIMUM LENGTH OF SLOPE ABOVE THE FENCE SHOULD BE 100 FEET.
- 6. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
- 7. SILT FENCES SHOULD BE REMOVED WHEN THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.

SILT FENCE



SEDIMENT TRAP OUTLET SUPPLY WATER TO WASH TEMPORARY SEDIMENT WHEELS IF NECESSARY TRAP AS NECESSARY 3" COURSE AGGREGATE MIN. 6" THICK DIVERSION RIDGE (WHERE REQUIRED) (MAY BE 50' WHERE DIVERSION RIDGE IS PROVIDED)

<u>PLAN VIEW</u>

NOTES:


. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

2. THE MINIMUM STONE USED SHOULD BE 3-INCH CRUSHED STONE.

3. THE MINIMUM LENGTH OF THE PAD SHOULD BE 75 FEET, EXCEPT THAT THE MINIMUM LENGTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH HIGH BERM IS INSTALLED AT THE ENTRANCE OF THE PROJECT SITE.

- 4. THE PAD SHOULD EXTEND THE FULL WIDTH OF THE CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS GREATER.
- 5. THE PAD SHOULD SLOPE AWAY FROM THE EXISTING ROADWAY.
- 6. THE PAD SHOULD BE AT LEAST 6-INCHES THICK.
- 7. THE GEOTEXTILE FILTER FABRIC SHOULD BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE BELOW THE PAD.
- 8. THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.
- 9. NATURAL DRAINAGE THAT CROSSES THE LOCATION OF THE STONE PAD SHOULD BE INTERCEPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUITABLE OUTLET
- 10. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
- 11. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT

GRAVEL CONSTRUCTION EXIT



EROSION CONTROL DETAILS

TAX MAP 214 LOT 11 (4 RIVERVIEW COURT) **DURHAM, NEW HAMPSHIRE**

PREPARED FOR. **ARTHUR MCMANUS** 29 FRONTIER STREET, RYE, NH 03870

LAND OF:

ARTHUR L. MCMANUS, JR. & DEBORAH MCMANUS 29 FRONTIER STREET, RYE, NH 03870

SCALE: NOT TO SCALE

DECEMBER 12, 2024 Surveying + Engineering + Land Planning + Permitting + Septic Designs


SCALE: N.T.S.





206 Elm Street, Milford, NH 03055 Phone: (603) 672-5456 Fax: (603) 413-5456 www.FieldstoneLandConsultants.com

PROJ. NO. 3886.02 SHEET: DT-1 FILE: 3886DT02.dwg PAGE NO. 2 OF 3




5. ANY ALTERATION OF THIS DESIGN OR CHANGE DURING CONSTRUCTION MAY REQUIRE APPROVAL OF VARIOUS TOWN/CITY BOARDS OR AGENCIES AND SHALL BE DISCUSSED WITH THE OWNER AND FIELDSTONE LAND CONSULTANTS, PLLC PRIOR TO

6. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE APPROPRIATE CITY DEPARTMENTS PRIOR TO CONSTRUCTION TO ARRANGE FOR NECESSARY INSPECTIONS.


7. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ACCURATE AS-BUILT INFORMATION OF ALL WORK, ESPECIALLY UNDERGROUND CONSTRUCTION OF UTILITY LINES, SERVICES, CONNECTIONS, ETC. AND APPROPRIATE TIES TO ABOVE GROUND PERMANENT STRUCTURES, FIELD SURVEY COORDINATES, OR SOME OTHER METHOD OF ESTABLISHING THE AS-BUILT CONDITION

8. THE CONTRACTOR AND OWNER ARE RESPONSIBLE FOR OBSERVING AND MANAGING THE PROJECT PER RSA 430:53 AND AGR 3800 REGARDING INVASIVE SPECIES (PLANTS AND INSECTS). NO INVASIVE SPECIES PLANT OR INSECT SHALL BE INTRODUCED






TYPICAL PAVEMENT SECTION



THE BINDER COURSE SHALL BE PLACED IMMEDIATELY AFTER TRENCH CONSTRUCTION AND ALLOWED TO STAND A MINIMUM OF 90 DAYS. A LEVELING COURSE SHALL BE APPLIED OVER THE TRENCH AFTER 90 DAYS AND THE ENTIRE ROAD OVERLAID TO THE LIMITS SHOWN ON THE PLANS.








1. SEE ROADWAY OR PARKING LOT SECTION FOR MATERIALS AND ASSOCIATED DEPTHS.

2. INFRARED JOINT AFTER PLACING PAVEMENT.

PAVEMENT MATCH







5'-0**"** HEADWALL SHALL BE STEEL REINFORCED AND CONFORM TO NHDOT STANDARD PLAN HW-2, LAST REVISED JUNE 16, 2010.

4'-3"

HEIGHT

HEADWALL HEADWALL

LENGTH

6'-0"

7'-0"

INCHES

HEADWALL - PRECAST CONCRETE (HW1)

FILL

FEET & INCHES

1'-7"


4'-6" 1'-10" 1'-6" 2'-1.50"


HEIGHT

TOP

2'-4" 1'-6" 2'-3.00"

1'-6" 2'-0.75"





- 1. DO NOT PLACE RAIN GARDEN SYSTEM INTO SERVICE UNTIL THE BMP HAS BEEN PLANTED AND ITS CONTRIBUTING DRAINAGE AREA(S) HAVE BEEN FULLY STABILIZED.
- 2. TO PREVENT DEGRADATION OF INFILTRATION FUNCTION:

A. DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATIONS WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION COMPONENTS OF THE SYSTEM.

B. DO NOT COMPACT THE EXCAVATION.

C. DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE RAIN GARDEN AREA DURING ANY STAGE OF CONSTRUCTION.

FROM UNHSC BIORETENTION SOIL SPECIFICATION FEBRUARY 2017

2.1 SOIL MEDIA SPECIFIED ACCORDING TO PERFORMANCE REQUIREMENTS Particle Size Distribution according to ASTM D422 (Standard Test Method for Particle-Size Analysis of Soils).

Particle Size Distribution by Separates:

- a. Exclude any material > 4.76 mm 0%
- Very Coarse Sand/Gravel: Gravel (2.0 to 4.76 mm) 5% maximum (percent by dry
- Sand (0.42 to 2.0 mm) 60 85% (percent by dry weight).
- Silt (0.075 to 0.42 mm) 20% maximum (percent by dry weight).
- e. Clay (less than 0.075mm) 5% maximum (percent by dry weight).

Table 1: Acceptable particle size distribution of final bioretention soil mix

	Sieve#	Sieve Size in (mm)	% Passing
	4	0.187 (4.76)	100
	10	0.079 (2)	95
	40	0.017 (0.42)	40 - 15
[200	0.003 (0.075)	10 - 20
	<200	Pan	0 - 5

RAIN GARDEN INVERT INFORMATION				
GARDEN #	ELEVATION			
	А	В	С	D
1	12.0	11.0	9.0	7.5

SCALE: N.T.S.

RAIN GARDEN TYPICAL SECTION

_	1	T.		ı	1
REV.	DATE	DESCRIPTION	0/0	DR	CK

CONSTRUCTION DETAILS

TAX MAP 214 LOT 11 (4 RIVERVIEW COURT) **DURHAM, NEW HAMPSHIRE**

PREPARED FOR:

ARTHUR MCMANUS 29 FRONTIER STREET, RYE, NH 03870

LAND OF: ARTHUR L. MCMANUS, JR. & DEBORAH MCMANUS 29 FRONTIER STREET, RYE, NH 03870

SCALE: NOT TO SCALE

DECEMBER 12, 2024

Surveying + Engineering + Land Planning + Permitting + Septic Designs



206 Elm Street, Milford, NH 03055 Phone: (603) 672-5456 Fax: (603) 413-5456 www. Fields to ne Land Consultants. com